1981 No. 299

HOUSING

The Homes Insulation Scheme (Amendment) Order (Northern Ireland) 1981

Made	*4th September 1981*
Coming into operation . . .	*19th October 1981*

The Department of the Environment in exercise of the powers conferred on it by Article 86(1), (2) and (7) of the Housing (Northern Ireland) Order 1981(**a**) and of every other power enabling it in that behalf hereby makes the following Order:

Citation and commencement

1. This Order may be cited as the Homes Insulation Scheme (Amendment) Order (Northern Ireland) 1981 and shall come into operation on 19th October 1981.

Amendment to the Homes Insulation Scheme (Northern Ireland) 1980

2. For the Schedule to the Homes Insulation Scheme (Northern Ireland) 1980, as contained in the Homes Insulation Scheme Order (Northern Ireland) 1980(**b**), there shall be substituted the Schedule.

Sealed with the Official Seal of the Department of the Environment for Northern Ireland on 4th September 1981.

(L.S.) *J. Kirk*

Assistant Secretary

(**a**) S.I. 1981/156 (N.I.3)
(**b**) S.R. 1980 No. 328

SCHEDULE

Materials specified for the insulation of roof spaces

Column 1 Material	Column 2 Thickness
Blofil (Agrément Certificate 78/607 Second Issue)*	80 mm
Blow-matic Blown Mineral Wool Fibre (Agrément Certificate 80/778)*	85 mm
Certain Teed Blowing Wool (Agrément Certificate 80/793 Second Issue)*	75 mm
CIA Blown Mineral Wool Fibre (Agrément Certificate 80/712)*	90 mm
Cibco Armax (Agrément Certificate 80/794)*	75 mm
Crown 75 (BS 5803 Part 1)	80 mm
Dodge City Loft Insulation (BS 5803 Part 1)	80 mm
Draco Fibreflow Rockwool (Agrément Certificate 80/806)*	80 mm
Energy Saver (BS 5803 Part 1)	80 mm
Freeman Rockfibre Blown Mineral Fibre (Agrément Certificate 80/780)*	75 mm
Gypglas 1000 (BS 5803 Part 1)	80 mm
Heatmax Spraymatic (Agrément Certificate 80/807)*	75 mm
Heat Saver (BS 5803 Part 1)	80 mm
Insulay (BS 5803 Part 1)	80 mm
Interlay (BS 5803 Part 1) (Cape Insulation Limited)	80 mm
Interlay (BS 5803 Part 1) (Newalls Insulation Company Limited)	80 mm
Marley Wrap (BS 5803 Part 1)	80 mm
Micafil (Agrément Certificate 79/680)	130 mm
PI Blown Mineral Wool Fibre (Agrément Certificate 80/711)*	80 mm
Poliglass Blown Glass-fibre (Agrément Certificate 80/741)*	80 mm
Rocksil Building Mat (BS 5803 Part 1)	80 mm
Rocksil Housewarm (BS 5803 Part 1)	80 mm
Rockwool Blown Mineral Fibre (Agrément Certificate 80/804)*	80 mm
Rockwool 002 Blown Mineral Fibre (Agrément Certificate 80/805)*	80 mm
Rockwool Rollbatt (BS 5803 Part 1)	80 mm
Sankey Loft Insulation (BS 5803 Part 1)	80 mm
Sankey Wrap (BS 5803 Part 1)	80 mm
Shelter Shield Class 1 (Agrément Certificate 80/709)*	80 mm
Solarwrap (BS 5803 Part 1)	80 mm
Supawrap (BS 5803 Part 1)	80 mm
Super Wool Rocksil Insulation Mat (BS 5803 Part 1)	80 mm

Column 1 Material	Column 2 Thickness
Super Glass Glass Fibre Insulation Mat (BS 5803 Part 1)	80 mm
Texas Loft Insulation (BS 5803 Part 1)	80 mm
Texas Supawarm (BS 5803 Part 1)	80 mm
Thermatic (Agrément Certificate 78/557 Third Issue)*	80 mm
Thermoken (Agrément Certificate 79/679 Second Issue)*	80 mm
Thermsave (Agrément Certificate 79/612)*	75 mm
Tilcon Trufill Perlite (Agrément Certificate 80/710)	80 mm
Trans-Thermal Blown Glass Fibre (Agrément Certificate 80/792)*	75 mm
U-Save Blown Cellulose Fibre Loft Insulation (Agrément Certificate 81/856)*	70 mm
Warmahome (BS 5803 Part 1)	80 mm
Warmcel (Agrément Certificate 80/808)*	75 mm
Wickes Rockwool Roof Insulation (BS 5803 Part 1)	80 mm
Wilko Loft Insulation (BS 5803 Part 1)	80 mm

*The conditions of the Certificate require the material to be installed by specialist contractors.

EXPLANATORY NOTE

(This note is not part of the Order.)

This Order substitutes a revised Schedule of specified materials on which grant may be paid for the Schedule to the Homes Insulation Scheme (Northern Ireland) 1980.

The substituted Schedule contains 8 new products, 7 of which are changes in brand names, and in 2 cases alters the thickness of the material required to be laid in order to qualify for grant.

One product, Cibco K19, has been deleted from the list and will no longer qualify for grant.